#### German Committee for Underground Construction e. V.



# Project risk management in underground construction

Heinz Ehrbar

Agenda



#### 1. Brief introduction

Why have we developed the DAUB recommendations?

#### 2. Content of the DAUB recommendations

#### 3. Discussion

#### «Firstly, things turn out differently, and secondly, never as you think» (Wilhelm Busch)



2023: 10 weeks standstill Follo Line Tunnel (Norway)



https://www.acciona.com/updates/articles/acciona-successfully-energization-railway-tunnels-follo-linenorway/?\_adin=02021864894

#### 2022: Shaft collapse Metro Sao Paolo, line 6



https://www.reuters.com/world/americas/part-sao-paulo-expressway-collapses-near-metro-construction-site-2022-02-01/

#### 2021: Water ingress at the Lötschberg base tunnel (Switzerland)



© Marc Meschenmoser /SRF

#### 2007: Shaft collapse Metro Sao Paolo, line 4



https://newsbulletin247.com/economy/44444.html

#### Dramatic incidents prevent project success





#### Consequences

- In some cases, there were fatalities or serious injuries
- Delays in the construction programme
- Enormous financial losses
- Impairment of third-party property
- Reputational damage for construction method(s), contractors, planners and clients



#### Risk events do not simply occur, they have a cause



#### Human error is the main cause of hazardous incidents



Objective hazard pot	ential				
objectively known					unknown
subjectively perceived				unrecognised	
considered			neglected		
Accepted without further measures	Definition of measures		Suppre	ssed risks	
	practical	unsuitab	e		
	used correctly	used incorrectly/not used			
¥	¥	۱			1
accepted residual risks	Safety through measures	Hazards from incorrect hu	man actions <i>i</i>	non-actions	Force majeure
Incindents		Incid	ents		
Quantity 25%		Quantity	75%		
Material damage 10%		Material damage	90%		
Personal injury 15%		Personal injury	85%		
		according to: Schneider, Jörg; Safety and reliability	n construction: Basic know	vledge for	

#### IMIA: Tunnel Loss Experience Causes of Underground Failures





Source: Reiner, Hartmut; Developments in the tunnelling industry following introduction of the tunnelling code of practice, IMIA Annual Conference, Amsterdam, 21. September 2011

# Lack of risk awareness led to serious problems in underground construction (2006 ff.)





Version-of-the-Tunnelling-CoP.pdf



Importance of risk management in national design and construction specifications



#### Mention of the word "risk / risks" in relevant performance models

HOAI Germany

SIA 112 Switzerland

 $\mathbf{O}$ 

3

#### The hierarchy of risk management

Strategic CRM

Project risk

management

(operational risk management)

Process-orientated RM

- Occupational health and safety

- IT security (ISO 27001) - Reporting security

- Environmental safety (ISO 14001)

Based on ONR 49000



Strategic risk management Company level (must fulfil the legal requirements)

Ensure compatibility through mutual coordination

#### Operational risk management at the project management level (regulated in the client's QM system)

Define harmonised targets and measurement and control parameters

Risk management in the provision of services (regulated in standards, guidelines, work instructions)

Risk management

#### The DAUB recommendations







#### Objectives and scope of the recommendations





#### Scope of the recommendations

The Recommendations are intended for everyone involved in the project (owner, designer, contractor, third party) for all work phases of a project, to:

- 1. demonstrate the imperative need for phasespecific project risk management,
- 2. clarify their role-specific duties and responsibilities for each project phase, and
- 3. introduce common, easy-to-use methods and tools for project risk management.

The Recommendations are applicable:

- principally, for all construction works,
- during all project phases from basic determination to commissioning,
- for all trades of the civil works,
- for all contract models in construction.



#### The basic principle of project risk management

**Risk management Risks** Threats **Opportunities** Event 👍 Event **Project requirements** Processes fulfilled (= project objectives achieved) measures define and implement measures to ... to to utilise control opportunities

Project idea with requirements (formulate project goals)



#### The curve of knowledge gain



# The additional knowledge gained helps to better achieve the project goals



# Know ledge

#### without project risk management



#### with project risk management

#### Project risk management methodology; Implementation of the ISO 31000 process





#### Establishing the project context





#### Typical cause / impact relationship



Ground conditions and existing but	ildings
Legal basis and anychanges	
Procedure	
Financing	
Politics / Economy	
Planning / Design	
Execution	
Buildingsupervision	
Order changes	
Contractual risks	
Interfaces	
Operation of nearby plants	
Natural hazards/accidents/incidents	
Force majeure	



#### 11 Project requirements

Guarantee agreed <b>quality</b>
Ensuring occupational health and safety
Protecting the environment from damage
Creating public and political <b>acceptance</b>
Ensure compliance with laws/ standards and guidelines
Protection of infrastructure and third-party rights
Guarantee of capacity in the existing network (operating programme/infrastructure)
Efficient structural and process organisation
Veeting the deadline targets
Compliance with <b>cost targets</b>

Ensure ordered functionality

#### **Risk identification**



DAUB

- Risk workshops (with structured what-if analysis, SWIFT)
- Brainstorming Brainwriting
- Checklists
- Evaluation of existing risk registers
- Exchange of experience with project organisations with similar tasks
- Obtain expert opinions (Delphi method) / Four-eyes principle
- Interviews
- Literature study / case studies

Picture: Wikipedia/tamara semina

#### **Risk analysis**

#### Semiquantitative method

	Probability P			
Impact I	very low	low	medium	high
high	4	8	12	16
medium	3	6	9	12
low	2	4	6	8
very low	1	2	3	4

Quantifying the impact (per objective) in classes

Qualitative assessment of probability in classes



#### Semiquantitative method

**Risk assessment** 

	Probability P			
Impact I	very low	low	medium	high
high	4	8	12	16
medium	3	6	9	12
low	2	4	6	8
very low	1	2	3	4



#### Additional measures absolutely necessary

#### Acceptance line



Emergency measures absolutely necessary



No additional measures - observe



#### Risk analysis and risk assessment



#### **Quantitative method (for specific questions)**



http://www.geomod.ch/geoprest/?DAT\_-\_Decision\_Aids\_for\_Tunnelling,



Ehrbar, H., Beeler, P., Neuenschwander, M., Bianchi, (2010, Proceedings ITA World Tunnel Congress, 2010 Vancouver

#### How to implement? The risk register as the key management tool





#### Options for action





# Example of mitigation measures for underground construction projects (not exhaustive)



Action two	Action strategy				
	avoid	reduce	transfer		
Appropriate Resources	<ul> <li>Use of qualified, experienced staff / continuous training</li> <li>Use of proven device types (state of the art)</li> <li>Use of new devices</li> </ul>	<ul> <li>Provision of special teams (e.g. injections,)</li> <li>Provision of (special) devices (e.g. injection devices, pumps,)</li> </ul>			
Material Measures	<ul> <li>Optimization of alignment</li> <li>Careful planning, taking safety and environmental aspects into account</li> <li>Use of safe, proven construction methods and installations</li> <li>suitable choice of material</li> </ul>	<ul> <li>Appropriate site investigations</li> <li>Optimization of alignment</li> <li>Systematic exploratory drilling in advance and monitoring during excavation</li> </ul>			
Organizational measures	<ul> <li>Define a clear risk policy (acceptance lines / alarm values)</li> <li>Systematic implementation controls Foureyes principle / Strategic Review Panel</li> <li>Provision of expert teams</li> </ul>	<ul> <li>Organization of rescue services</li> <li>Alliance contract</li> <li>Provision of expert teams</li> </ul>	<ul> <li>Contractually agreed risk allocation (e.g. SIA 118/198)</li> <li>Insurance coverage</li> </ul>		

#### Communication of threats depending on the impact and decision-making level



IMIA Webinar

#### **Risk Communication**





### Each individual hazard must be countered with suitable and measures





#### Nevertheless, risk events can occur





#### Communication in the case of incidents





#### Typical ground related hazard scenarios 1/3



Hazard scenario	conventional	mechanical	Mitigation measures
Rockfall			<ul> <li>Rock cleaning</li> <li>Head protection at a minimum angle of 180°, immediately after the cavity is opened</li> </ul>
Breakdown			<ul> <li>Installation of a sufficiently dimensioned ground support</li> </ul>
Downfall			<ul> <li>Installation of a sufficiently dimensioned ground support</li> <li>if necessary, ground improvement measures</li> </ul>

Image source: BLS AT, final report on rock mechanics, excavation, stabilisation, 2009

#### Typical ground related hazard scenarios 2/3



Hazard scenario	conventional	mechanical	Mitigation measures
Stress-induced detachment/ Rock burst			<ul> <li>Waiting time</li> <li>Customised rock support after each round</li> <li>Possible expansion holes</li> <li>Installation of steel ribs</li> <li>Anchors with high expansion capacity</li> </ul>
Unstable tunnel face	© IG GBTS		<ul> <li>Drainage holes</li> <li>Support of the tunnel face with long, grouted self-drilling anchors</li> <li>Selection of a TBM with sufficient face support (in loose material)</li> </ul>
Sinkholes		Kovari/Bosshard: Zimmerberg Tunnel	<ul> <li>Pipe umbrella / large pipe umbrella via TBM tunnelling</li> <li>Conventional support of the face with long, grouted self- drilling anchors</li> <li>Selection of a TBM with sufficient face support (in loose material)</li> </ul>

Image source in general: BLS AT, final report on rock mechanics, excavation, stabilisation, 2009

#### Typical ground related hazard scenarios 3/3



Hazard scenario	conventional	mechanical	Mitigation measures
High deformations / High ground pressures (Squeezing or swelling rock)	© IG GBTS		<ul> <li>Installation of a deformable break- out protection</li> <li>Additional cut-out for deformations (overcut with TBM)</li> <li>Reprofiling if necessary</li> </ul>
Water pressure (local)	The second secon	y to	<ul> <li>flow-reducing injections</li> <li>Ground freezing</li> <li>Drainage holes</li> </ul>
Sudden water ingress at high pressure			<ul> <li>flow-reducing injections</li> <li>Preliminary drainage holes</li> </ul>

Image source: BLS AT, final report on rock mechanics, excavation, stabilisation, 2009

Who has what responsibility? - Key role of the client



The client is the first to come into contact with the project and must initiate the process. Project risk management is one of the project manager's management tasks!



All internal partners must be integrated and, if necessary (depending on the context), also external partners to the project.

#### Phase-related goals of project risk management

Phase-related goals of project risk management						
Project stages AHOService phases (HOAI)(general process)(Design services)		Goals (Design and construction )	Goals Risk management			
4 Initiation	0 Analysis of the needs	Needs, goals and framew ork conditions defined, solution strategy determined	-			
1. Initiation	1 Collection of the basics	Clarification of the task (project planning basics/inventory)	Risk management implemented by the owner			
	2 Feasibility design	Proof of the feasibility of the best variant cost estimate	Risk analysis carried out for all variants, risk costs recorded for the first time in the cost estimate			
2. Design	3 Preliminary design	Project optimized and described ready for implementation, deadlines defined, cost calculation	Detailed risk analysis including planning of measures carried out - risk costs recorded in cost calculation			
	4 Technical design	Obtaining of all planning approvals	Acceptance risks eliminated			
	5 Detailed design	Definition of the project with construction drawings and workshop drawings	Risk-reducing/opportunity-utilizing measures included in the implementation plan			
3. Procurement	6 Procurement	Contract model and risk limitation defined Qualification and aw ard criteria defined	Handover of the findings from the client's risk analysis to the bidders			
	7 Contract aw ard	Selection of the contracor taking into account the most advantageous offer	Selection of the contractor, taking into account his contribution to the exploitation of opportunities/threats prevention			
4. Construction	8 Object supervision - construction supervision and documentation	Structure realised according to the work contract, in compliance with all project requirements	Im plementation of an integral risk management including all parties involved - final evaluation			
5. Commissioning	9 Asset managment	Ensure operation Maintain usability and value	Consider operational experience for risk management of future projects			

# Please support the implementation of project risk management!

«.... so that in future we no longer fall short of what we have achieved but, on the contrary, that those to come do even better than us!» Mr. Sulzer Ziegler, Breakthrough of the Simplon Tunnel, 1905

## Many thanks

Picture: IG-GBTS